



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 27 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
2-27-74

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of SW Casing Pulling Co., Inc., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Gillespie Well No. 1

Location: CSW-SE Sec. 10 Twp. 3 Rge. (E)(W) 27

County: Decatur Total Depth 3865 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

232'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3864'--5 1/2" Production casing cemented on bottom with 175 Sx. Top of cement @ 2964'. Top perforations from 3612' to 3614'.

Sand well back to 3600' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

*W. J. Orchale*  
Conservation Division Agent