

State of Kansas



15-039-20024-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM I. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name: Delbert Well No. 1

Location: NE-NE-SE Sec. 15 Twp. 3 Rge. (E)(W) 27

County Decatur Total Depth 3840' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

254'--8 5/8" Surface pipe, cement circulated with 215 Sx. Dakota section from 1200' to 1375'.

Circulate hole with heavy mud. Pull DP to 1750' and attempt to balance plug using 20 Sx. cement plus 6% gel and 4% Ca Cl/2. If plug holds after 3 hours pull DP to 1400' and displace 60 Sx. cement plus 6% gel thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent

Rec'd  
10-19-67