


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-137 00116 - 00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

NORTON

County, Sec. 10 Twp. 3 Rge. 25 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner R. W. SHIELDS

Lease Name Mizell Well No. 1

Office Address RULE BLDG., WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 28 19 53

Application for plugging filed (Mar.-verbal) April 1 19 54

Application for plugging approved April 2 19 54

Plugging commenced March 7 19 54

Plugging completed April 1 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3902 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		-0-	251'	8 5/8	251	-0-
		-0-	3712'	5 1/2	3712	1510'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back with chat to 3500'. Dumped 4 sacks of cement. Shot pipe off at 1510'. Pulled pipe and mudded hole to 250'. Dumped 25 sacks of cement and mudded to top. Dumped 10 sacks of cement at base of celar.

04-17-1954

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address RR#4 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #4, Hutchinson, Kans.

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 54

My commission expires August 12, 1957

Dorothy Self
Notary Public.

PLUGGING
FILE SEC 10 T. 3 R. 25 W
PAGE 24 LINE 28

15-137-00114-00-00

DRILLER'S LOG

Company: Peel-Harman Oil Producers

SW-SW-NW

Farm: Mozell Well No: 1

Sec. 10, Twn. 3, Rge. 25

Total Depth: 3902'

County: Norton,

Kansas

Comm: 11-24-53 Comp: 12-6-53

Contractor: Peel Brothers, Inc.

Elevation:

Casing:

8 5/8" @ 251' Cem.
5 1/2" @ 3712' Cem.

Production:

Figures below indicate bottom of formation

Surface clay and sand	0'	65'
Sand		165
Sand streaks		200
Shale		625
Shale and Bentonite streaks		725
Shale		880
Shale and shells		1125
Shale and sand streaks		1425
Shale and shells		1600
Shale		1740
Sand		1860
Shale and sand streaks		2015
Shale and red-bed		2078
Anhydrite		2112
Shale and shells		2345
Shale		2435
Shale and Bentonite		2540
Shale and lime streaks		2565
Shale and sand and lime streaks		2685
Shale and lime streaks		2800
Shale		2845
Shale, lime and Pyrite streaks		3020
Lime		3085
Lime and shale		3260
Lime		3650
Lime and shale		3700
Lime		3795
Lime and conglomerate		3870
Conglomerate		3880
Granite wash		3902
Total depth		3902

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.

BY R. E. Sutton

SUBSCRIBED AND SWORN TO before me this 14 day of December 1953

My commission expires September 28, 1957

Norma L. Rees

RECEIVED
STATE CORPORATION COMMISSION

APR 29 1954

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 10 T 3 R 25u
BOOK PAGE 24 LINE 28