

15-039-20649-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Decatur SEC. 12 TWP. 3S RGE. 27W E/W
 Location as in quarters or footage from lines:
 NW SW

x			

Locate Well
 correctly on above
 Section Platt.

Lease Owner S & W Drilling Co., Inc.
 Lease Name Montgomery Well No. 12-12
 Office Address P O Box 132 Oberlin, Kansas 67749
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 4-28-82
 Application for plugging filed 6-10-82
 Plugging commenced 9:00 AM 6-9-82
 Plugging completed 12-30 PM 6-9-82
 Reason for abandonment of well or producing formation _____

Dry Hole

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation none Depth to top _____ bottom T.D. 3850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface sand	water	30	190	8 5/8	263	0
Dakota & Ceder Hills	Water	1240	2010	7	2240	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. 7" Casing was squeezed from the surface with 2 sx hulls followed by 20 sx gel followed by 45 sx 50/50 poz 3%cc 4% gel followed by 13 sx gel followed by 35 sx cement as above followed by a 7" plug followed by 10 sx cement as above. Annulus between 8 5/8" & 7" was plugged with 40 sx cement as above and 10 sx cement as above were pumped into the rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing Co.

STATE OF Kansas COUNTY OF Decatur, ss.
James L. Reeves (employee of owner) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James L. Reeves
P.O. Box 16 Oberlin, KS
 (Address)

SUBSCRIBED AND SWORN TO before me this TENTH day of JUNE, 19 82

Helen J. Bull
 Notary Public.

My Commission expires: 12/22/82

Rec'd
 6-10-82

