

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-039-20,752-00-00

LEASE NAME Gillespie

WELL NUMBER #1-10

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 10 TWP. 3 RGE. 27 (X) or (W)

COUNTY Decatur

Date Well Completed 11-06-84

Plugging Commenced 11-06-84

Plugging Completed 11-06-84

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 300 Sutton Place, Wichita, KS 67202

PHONE#(316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Gibb Lieker - State Pluggger

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations. **See ACO-1**

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	288'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
1st plug set @ 4000' w/25 sx., 2nd plug set @ 2310' w/25 sx., 3rd plug set @ 1660' w/100 sx., 4th plug set @ 300' w/40 sx., 5th plug set @ 40' w/10 sx., 1 sx hulls & 1 plug. 10 sx in rathole Total 210 sx 50-50 poz, 6% Gel, 3% CC, 2 sx cello-flake. Cemented by Allied Cementing Co. Complete @ 8:45 a.m. 11-06-84. State Pluggger - Gibb Lieker.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co.

License No. N/A

Address P.O. Box 31, Russell, KS 67665

STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Sedgwick

DEC 11 1984 12-11-84

Dan A. Bowles (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dan A. Bowles
 Dan A. Bowles

(Address) 300 Sutton Place, Wichita, KS 67202



My Commission Expires: 3-30-85

Mercedith K. Crisp
 Notary Public
 Mercedith K. Crisp

CONFIDENTIAL