

6-13

4-060433

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-039-20,889-06-00

SW SW SE /4 SEC. 05, 03 S, 26 W
330 feet from S section line
2310 feet from E section line

Operator license# 4767

Lease Hix Farms well # 1

Operator: Ritchie Exploration, Inc.

County Decatur

Address: 125 N. Market
Suite #1000
Wichita, Kansas 67202

Well total depth 3800 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 239 feet

123.50

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 8:00P.M Day: 13 Month: June Year: 93

Plugging proposal received from: Lloyd Delette

Company: Murfin Drilling Company, Inc. Phone:

Were: Order 190 sxs. 60/40 posmix - 6% gel with 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:45P.M, Day: 13, Month: June, Year: 93

Actual plugging report:

- 1st. plug at 2160' with 25 sxs.
- 2nd. plug at 1455' with 100 sxs.
- 3rd. plug at 290' with 40 sxs. - Surface pipe to 239'.
- 4th. plug at 40' with 10 sxs.
- Rathole with 15 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: 2603 GL

I did [X] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1993

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE SEP 14 1993

INV. NO. 38623



(agent)

Form CP-2/3