

4-070106

8-18

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-039-20,911-00-00

W2 SE SE NE/4 SEC. 10, 03 S, 26 W
2970 feet from S section line
500 feet from E section line

Operator license# 30606

Lease: Price Trust Well # 1-10

Operator: Murfin Drilling Company, Inc.

County: Decatur 129.81

Address: 250 N. Water - #300
Wichita, Kansas 67202

Well total depth 3994 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 255 feet

ABAND. oil well, Gas well, Input well, SWD, D&A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: 250 N. Water - Suite #300 - Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 18 Month: August Year: 1998

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company, Inc. Phone: 785-483-6446

Were: Ordered 190 sxs 60/40 pozmix - 6% gel - 1/4# floseal per sack - one 8 5/8" W.P.
Spot plug through drill pipe with heavy drilling mud between all plugs.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 6:30 P.M., Day: 18, Month: August, Year: 1998

Actual plugging report: No arbuckle cut.

1st. Plug at 2130' w/25 sxs. - Anhydrite 2113' - 2143'.

2nd. Plug at 1409' w/100 sxs. - Surface pipe at 255' + 50'.

3rd. Plug at 305' w/40 sxs. - Dakota +250'.

4th. Plug at 40' w/10 sxs and 8 5/8" wiper plug.

15 sxs in rathole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING Elevation: 2559 GL

I did [] / did not [X] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE SEP 01 1998

INV. NO. 51236

8-18

8-31-98