

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,724-00-00

W 1/2 SE SW, Sec. 9, T 3 S, R 26 W 1/2
760 feet from N/S section line
1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name Shirley Well # 24-9

Operator: Diamond Shamrock Exploration
Name & P.O. BOX 613
Address Amarillo, Tx. 79173

County Decatur

Well Total Depth 3725 feet 121.07

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Big Springs Drilling License Number Tag # 144

Address Box 8287 Munger Station #29, Wichita, Ks. 67208

Company to plug at: Hour: 2 PM Day: 2 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Harry Kirkman

(company name) Big Springs Drilling (phone) (806) 378-3848

were: 8 5/8 " 343' SP CUC w/250 sks 60/40 pozmix 3% cal cl (By Halliburton)

Ordered 195 sks 50/50 pozmix 4% gel - 3% cal cl w/1 sks cello-flake and 8 5/8 plug.

Spot with drill stem-turn hole over - heavy mud between all plugs no arbuckle, - no

show-no gas kick- no circulation problems Elev. 2535' Anhy 2076

Signed Marvin Schmidt
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 3:15 PM Day: 2 Month: March Year: 19 84

ACTUAL PLUGGING REPORT Ordered 195 sks 50/50 pozmix 4% gel 3% cal cl. - 1 sk cello-flake and 8 5/8 plug spotted with drill stem- turned hole over - heavy mud between all plugs 1st plug @ 2100' w/25 sks cement

2nd plug @ 1410' w/100 sks cement w/1 sk cello-flake

3rd plug @ 350' w/50 sks cement

4th plug solid bridge hull's plug @ 40' w/10 sks cement

10 sks in Rat Hole (circulate) (Cemented by Halliburton Cementing Company)

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1984
3-12-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Marvin Schmidt
DOIC (TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 3-13-84

INV. NO. 0721