

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 039-20, 718-00-00

NW 1/4 Sec. 9, T 3 S, R 26 W E
1980 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5541

Lease Name ARNOLD-WEILERT Well # 1

Operator: WEILERT ENTERPRISES
Name &

County DECATUR

Address P.O. BOX 652
HAYS, KANSAS
67601

Well Total Depth 3900 feet 126.75

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor HELBERG DRILLING License Number TAG # 269 5669

Address P.O. BOX 32 MORLAND, KANSAS

Company to plug at: Hour: 10:30 AM Day: 11th Month: JAN Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO BUSTER WEILERT

(company name) WEILERT ENTERPRISES (phone) 913-628-3324

were: 8 5/8" 252 FT SQ. CUL. 11/145 5% COMMON GEL - CA-CL. BY ALLIED OIL
ORDER 190 5% 50/50 FORMIX GEL - CA-CL. -> 2% CELLO FLAME AND 8 5/8" PLUG

SPOT WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN CMT. PLUG
NO SHOW OR BLOW - NO CIRCULATION PROBLEMS, ELEV. 2571' ANTH 2159'
NO AIRBUCKLE.

Signed Marvin Schmidt (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:30 AM Day: 11th Month: JAN Year: 1984

ACTUAL PLUGGING REPORT

ORDERED 190 5% 50/50 FORMIX 6% GEL - 3% CA-CL. - 2% CELLO FLAME AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN CMT. PLUG

1st Plug @ 2130 FT 11/20 5% CMT., 2nd Plug @ 1420 FT 11/100 5% CMT.

3rd Plug @ 270 FT 11/50 5% CMT., 4th Plug HULL'S-PLUG @ 40 FT 11/10 5% CMT.

10th RAT-HOLE (CIRCULATE) 2% CELLO FLAME BLENDED IN CMT.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

JAN 16 1984

CONSERVATION DIVISION Wichita, Kansas

1-16-84

INVOICED signed Marvin Schmidt (TECHNICIAN) DOIC

DATE 1-18-84

INV. NO. 91681W