

To: 6 031300
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE SE NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-29-89
API NUMBER 15- 039-20,857-00-00
SEC. 8, T 3 S, R 26 W/XX
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30129
Operator: Eagle Creek Corp
Name & Address 107 N. Market Suite 509
Wichita, Ks. 67202

Lease Name HIX Well # 1
County Decatur 12/88
Well Total Depth 3750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 5422
Address Wichita, Ks.

Company to plug at: Hour: AM Day: 29 Month: Oct. Year: 19 89

Plugging proposal received from Wayne Shively
(company name) Abercrombie (phone) _____

were: 8 5/8" set at 281' w/180 sks cwc. circ hole w/no less than 36 vis mud w/no loss
or gain of fluid. Balance plugs w/mud, keep hole full. Order 190 sks 60/40 poz 6% gel
3% cc. 8 5/8" wiper plug. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:00 AM Day: 29 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 2125' w/25 sks

1300' w/100 sks and hulls

325' w/ 40 sks

40' w/10 sks

Circ 15 sks in rathole w/pipe

Remarks: Anhy 2110' - 43' Elev. 2566 EL
(If additional description is necessary, use BACK of this form.)

INVOICED (Stamp) Both observe this plugging.

DATE 7-24-90
INV. NO. 28705

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow