

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20796-00-00
Spot: CW2NWNE Sec/Twnshp/Rge: 8-3S-26W
4620 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: MONTGOMERY Well Number: 1-8
County: DECATUR Total Vertical Depth: 3959 feet

Operator License No.: 3602
Op Name: PHILPOTT OIL & GAS CO INC
Address: PO BOX 450 408 MAIN
ATWOOD, KS 67730

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 256
Production: Size 4.5 feet: 3919
Liner: Size feet:

\$128.67

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/18/2001 3:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 11 yards Redi-Mix - 6 sxs common cement with 3000# sand with 40 gal water.
Add extra water as needed.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/18/2001 4:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 256' w/175 sxs cwc. 4 1/2" set at 3919' w/600 sxs cwc.
Prod. Perfs 3547' - 3693'.
Filled 4 1/2" with 11 yards Redi-Mix.
Plug complete.

INVOICED
DATE 6-6-01
INV. NO. 2001061887

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 6 2001
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

100

MAY 30 2001

replacement card

MURFIN DRILLING COMPANY
WICHITA, KS 67202

8-03 -26W
C W/2 NW NE

#1-8 MONTGOMERY

site: 8-3/4 N & 1-1/2 E OF JENNINGS, KS

city: DECATUR

API 15-039-20796

confr: COMPANY TOOLS

field: WC (LIPPELMANN NW DISC)

geol: RICH BELL

fr date 09/26/86 spd date 09/29/86 drig comp 10/06/86 card issued 11/27/86 last revised 01/13/88

ELV: 2595 KB LOG

tops.....	depth/datum
ANH.....	2133 +462
TOP.....	3311 -716
HEEB.....	3480 -885
TOR.....	3511 -916
LANS.....	3522 -927
BKC.....	3716 -1121
CONG.....	3854 -1259
ARB.....	3911 -1316
PBTD.....	3875 -1280
RTD.....	3959 -1364

IP status:

OIL, P 56 BOPD, NW, LKC 3884-3893 OA,
CSG: 8-5/8" 256 / 175 SX, 4-1/2" 3919 / 600 SX, DV
TOOL AT 2138 / 425 SX
NO CORES
DST (1) 3479-3538 (TOR), / 30-30-30-30, REC 80' M
ISIP 781# FSIP 716# IFP 86# -86# FFP 97# -97# IHP
1833# FHP 1822# BHT 104 *

INFO RELEASED: 1/13/88 - WAS OIL WELL - TIGHT HOLE

(over)

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS