

8-8

6 070855

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 039-20,866 -00-00

SW SE NE, SEC. 30, T 3 S, R 26 W/Ex

2970 feet from S section line
990

feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9860

Lease Name Lund Well # 1

Operator: Castle Resources

County Decatur 130.00

Name & Address R.R. #1 Box 90

Well Total Depth 4000 feet

Hays, Ks. 67601

Conductor Pipe: Size 0 feet

Jerry Green

Surface Casing: Size 5/8 feet 255

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Op License Number 8241

Address Russell, Ks

Company to plug at: Hour: AM Day: 9 Month: August Year: 19 90
John Collins

Plugging proposal received from Emphasis Oil Co.

(company name) (phone)

were: 8 5/8 - 255 s.p. cwc w/160 sks 60/40 poz 3% gel 25 cc by Halliburton.

K.C. Well, Elv. 2590 Anhy 2171; No cir problems; mud 9.6 lbs. - 48 vis.

12 water loss Proposal 200 sks 60/40 poz 6% gel 3% cc and 8 5/8 plug. Spot with drill stem; circulate; heavy mud between all plugs. 25 sks at 2180 ft.

100 sks w/f.c. at 1440 ft. 40 sks at 300 ft. 10 sks w/w.p. at 40 ft. 15 sks rathol
10 sks in water well. circ.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 12:00AM Day: 8 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Emphasis ordered 200 sks 60/40 poz 6% gel

3% cc. 1sk f.c. and wiper plug. Spotted with drill stem, heavy mud between all plugs

(circ). 1st plug at 2180 ft w/25 sks cement.

2nd plug at 1440 ft w/100 sks cement w/1 sk f.c.

3rd plug at 300 ft w/40 sks cement.

4th plug w.p. at 40 ft. w/10 sks 15 sks in rathole (circ) 100 sks in water well.

Remarks: Cmt by Halliburton Cement.

additional description is necessary, use BACK of this form.)

I () / did not observe this plugging.

DATE: AUG 24 1990

INV. NO. 29058

J.G.S.

Signed Marion J. Schmidt (TECHNICIAN)

STATE CORPORATION COMMISSION
8-17-90
AUG 17 1990