

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-30151-00-00
Spot: NESW Sec/Twnshp/Rge: 2-31S-8W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease Name: VALDOIS A Well #: 1
County: HARPER Total Vertical Depth: 4825 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

PROD Size: 4.5 feet: 4526 100 SX CMT
SURF Size: 8.625 feet: 250 225 SX CMT

156 81

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2004 11:15 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Perfs 4423'-4428'
Plugging Sand to 4380' & 4 sxs
Method: 1375' & 35 sxs
925' & 35 sxs
Circ 300'

RECEIVED
KCC DISTRICT #2
MAY 11 2004

WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON Witness Type: NONE
Date/Time Plugging Completed: 04/23/2004 11:15 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

The perforations were covered with sand from 4526' to 4379' and capped with 4 sacks of cement. 4-1/2" casing recovered from 2200' and pulled to 1375' where 35 sacks of cement was spotted. Pulled casing to 925' and spotted 35 sacks of cement. Pulled casing to 300' and circulated cement to surface. Pulled casing and topped off.

60/40 posmix with 4% gel.

Top	Bot	Thru	Comments
4423	4428		

Remarks: ALLIED CEMENT #15326

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE 5-12-04

INV. NO. 2004061556