

6 050174

API NUMBER 15-137 20 352 00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C. SE-NE, SEC. 9, T. 3 S. R. 25 W. #

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name Gallentine Well # 1-9

Operator: Diamond Shamrock Expl. Co. County Norton

Name & Address P.O. Box 400

Well Total Depth 3910 <sup>127.08</sup> feet

Amarillo, Texas 79188-0001

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 300 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor A L Abercrombie License Number \_\_\_\_\_

Address 801 Union Center - Wichita Kan 67202 Regtag 179

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from James Skies

(company name) Diamond Shamrock (phone) \_\_\_\_\_

Work Order 195 sacs 50/50 Pos mix 6% @ - 1 sac Flo-cel - 8 5/8 Plug 1 sac hulls.

Run the Potts circulate hole with heavy mud with heavy mud between all plugs - good circulation and no fluid loss. 1st plug @ 2060 w/ 25 sacs 2nd plug @ 1350 w/ 110 sac - 3rd plug @ 350 w/ 40 sac - 4th Plug @ 40' w/ 8 5/8 Plug 1 sac hulls and 10 sac - with 10 sac circulated in rat hole.

Plugging Proposal Received by Gelbert P. Leiker (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:15 PM Day: 26 Month: Feb Year: 19 85

ACTUAL PLUGGING REPORT

1st Plug @ 2060' w/ 25 sac

2nd Plug @ 1350' w/ 110 sac 1 sac flo cel

3rd Plug @ 350' w/ 40 sac

4th Plug @ 40' w/ 8 5/8 Plug 1 sac hulls & 10 sac

10 sac in rat hole - By Halliburton

Remarks: \_\_\_\_\_

I (did not) observe this plugging.

DATE 3-5-85 INV. NO. 7239 2-26

Signed Gelbert P. Leiker (TECHNICIAN) 2-28-85

RECEIVED  
STATE CORPORATION COMMISSION  
03-04-1985  
MAR 0 1 1985  
CONSERVATION DIVISION  
Wichita, Kansas