

4-061126

12-2

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-137-20,405-00-00
255'S.of
N2 NW /4 SEC. 05, 03 S, 25 W
4695 feet from S section line
4620 feet from E section line

Operator license# 5144

Lease: Kennedy Well # 1-5

Operator: Mull Drilling Company, Inc.

County: Norton 128.93

Address: P.O. Box 2758
Wichita, Kansas 67201-2758

Well total depth 3967 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 344 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Pickrell Drilling Company, Inc. License# 5123

Address: Wichita, Kansas 67202

Company to plug at: Hour: 7:45 A.M. Day: 2 Month: December Year: 1997

Plugging proposal received from: Doyle Folkerts

Company: Pickrell Drilling Company, Inc. Phone: -

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 9:45 A.M., Day: 2, Month: December, Year: 1997

Actual plugging report:

- 1st. Plug at 2150' w/25 sxs. - Anhydrite 2128' - 2143'.
- 2nd. Plug at 1410' w/100 sxs. - Dakota 1108' - 1408'.
- 3rd. Plug at 400' w/40 sxs. - Surface pipe 344'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 10 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2558 GL

I did [] / did not [X] observe the plugging.

[Signature]
(agent)
Form CP-2/3

STATE CORPORATION COMMISSION
REGISTERED
DEC 12 09 1997
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 12-15-97

INV. NO. 48683

12-2