

4-032196

E-19,658

12-26

API Number: 15-039-20,440-00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NW SW SE /4 SEC. 14, 03, 27 W
990 feet from S section line
2310 feet from E section line

Operator license# 30606 Lease: Elvin Well # 3

Operator: Murfin Drilling Company, Inc. County: Decatur 132.99

Address: 250 N. water - Suite #300
Wichita, Kansas 67202
Well total depth 4092 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 212 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 26 Month: December Year: 1996

Plugging proposal received from: John Turner

Company: Murfin Drilling Company, Inc. Phone:

Were: Order 275 sxs 60/40 pozmix - 10% gel - 500# hulls.

Vertical stamp: 46-07-97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:50 A.M., Day: 26, Month: December, Year: 1996

Actual plugging report: 8 5/8" set at 212' w/200 sxs. cwc. 4 1/2" set at 4080' with 175 sxs. PBTD 4038'. Critical control shots at 1380' and 2150'. Squeezed 4 1/2" with 225 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 600#. Held. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 100#. Held. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did not observe the plugging.

Carl Goodrow (agent)

Form CP-2/3

INVOICED
DATE JAN 08 1997
INV. NO. 47283