

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-00017-00-01  
Spot: SWSWNE Sec/Twnshp/Rge: 6-13S-16W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: WINDHOLZ OWWO Well #: 1  
County: ELLIS Total Vertical Depth: 3570 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 225 MAIN  
RUSSELL, KS 67665

L1 Size: 4.5 feet: 2600  
PROD Size: 5.5 feet: 3568 w/100 sxs cmt  
SURF Size: 8.625 feet: 197

03  
H 116

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/18/2004 9:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: TIM SCHECK Company: SCHECK OIL OPERATIONS Phone: (785) 483-3404

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
4 1/2" cemented 2600' to surface.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/18/2004 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

TIH with tubing and bit. Hit hard bridge at 950'.  
Indicated casing was collapsed.  
Decided to P&A.  
Tubing at 950' - mixed and circulated cement with 50 sxs cement.  
POOH. Swaged onto 4 1/2" and pumped 50 sxs cement.  
Max. P.S.I. 500#. S.I.P. 300#.  
Annulus full of cement.

RECEIVED  
AUG 20 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE 8-23-04

INV. NO. 2005060386

Form CP-2/3

AUG 19 2004

J.L. KING OIL OPERATIONS  
BOX 75, RUSSELL, KS.

#1 WINDHÖLZ "OWWO"

6-13-16W  
SW SW NE

CONTR RAPID WELL SERVICE

CTY ELLIS

SECL P. D. NIXON

FIELD EMMEPAM TWST

S 2026

CM 4/9/78

CARD

ISSUED 7/7/75

IP P 13 BOPD

API NOT ASSIGNED;

LKC - INTV UNKNOWN

+	+	+
+	+	+
+	+	+

	TOPS	DEPTH	DATUM
ANH		1185	+ 841
HEEB		3215	-1189
TOR		3255	-1209
DOUG		3250	-1224
LANS		3255	-1259
ARB		3517	-1491
TD		3570	-1544

OLD INFO: OPERATOR WAS VICTOR DRLG. &  
DEEP ROCK; SPD ?, SET 8" 197. 5" 3568;  
COMPLETED FOR 600EOPD/12/19/52  
DST (1) 3272-3510/1', 1800'esy 0, SIP  
1005  
DST (2) 3526-37/1', 60'SL OCM, 280'  
OCM, 30'W, SIP 780 $\frac{1}{2}$   
MICT - PB, PF 20/3291-96, SWB 480PH,  
NAT, AC 500

NEW INFO: RE-ENTERED 4/9/78, WSH DWN,  
MICT - CO, PF (LKC) INTERVAL UNKNOWN,  
NAT, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS