

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23415-00-00
Spot: NESW Sec/Twnshp/Rge: 19-10S-17W
1980 feet from S Section Line, 1920 feet from W Section Line
Lease Name: BERKER Well #: 1
County: ROOKS Total Vertical Depth: 3680 feet

Operator License No.: 33401
Op Name: ERNST, FRED A.
Address: 1234 WALKER AVE.
WALKER, KS 67674

SURF Size: 8.625 feet: 256

#119⁶⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/15/2004 5:45 AM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: DARRELL ANDERSON Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 421-2234

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 08/15/2004 7:45 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 1400' w/25 sxs.
2nd. Plug at 900' w/100 sxs.
3rd. Plug at 310' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.


RECEIVED
AUG 20 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE

8-23-04

INV. NO.

2005060382

AUG 18 2004