

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23053-00-00
Spot: NESWSENW Sec/Twnshp/Rge: 4-13S-17W
3090 feet from S Section Line, 3490 feet from E Section Line
Lease Name: MARION STAAB Well #: 2-A
County: ELLIS Total Vertical Depth: 3613 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

MSCC Size: feet: 1261 300 SX
PROD Size: 5.5 feet: 3593 100 SX
SURF Size: 8.625 feet: 241 175 SX

\$117⁴²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2004 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GRADY BOLDING Company: BOLDING, GRADY CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 400# hulls.
Port collar at 1261' set with 300 sxs.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2004 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Annulus full of cement.
Swaged onto 5 1/2" - mixed and pumped 285 sxs cement with 400# hulls.
Max. P.S.I. 800#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3593	3613		
3329	3572		

RECEIVED
AUG 20 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 08-23-04

INV. NO. 2005060-380

Form CP-2/3

AUG 19 2004

ISERN-SCHULTZ OIL & GAS, INC. 4-13-17W
 BOX 486 #2 "A" MARION STAAB 450' FSL &
 ELLINWOOD, KS 67526 850' FEL, SE NW
 CONTR PIONEER DRILG. CO., INC. CTY ELLIS

GEOL _____ FIELD CATHERINE NW

E 2075 KB CM 6/16/82 CARD ISSUED 8/12/82 IP P 20 BO & 10 BWPD
 2070 GL ARB OH 3593-3601
 API 15-051-23,053

+	+
+	+
+	+

SMP	TOPS	DEPTH	DATUM
ANH		1262	+ 813
B ANH		1308	+ 767
TOP		3041	- 966
HEEB		3284	-1209
TOR		3302	-1227
DOUG		3318	-1243
LANS		3329	-1254
BKC		3572	-1497
CONG		3576	-1501
ARB		3587	-1512
RTD		3601	-1526

8-5/8" 241/175sx, 5 1/2" 3593/100sx

NO DST'S
 MICT - CO, (ARB OH) AC 500G (28% INS),
 POP, P 20 BOPD & 10 BWPD, 7/9/82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS