

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-039-20,752-06-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Gear Petroleum Co., Inc. OPERATORS LICENSE NO. 5151
ADDRESS 300 Sutton Place, Wichita, KS 67202 PHONE # (316) 265-3351
LEASE (FARM) Gillespie WELL NO. 1-10 WELL LOCATION NW ~~SE~~ COUNTY Decatur
SEC. 10 TWP. 3S RGE. 27W (E) or (W) TOTAL DEPTH 4085' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____ (dl)
SURFACE CASING SIZE 8-5/8" SET AT 288' CEMENTED WITH 140 SACKS
CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
PERFORATED AT N/A

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 25 sx @ 4000'; 25 sx. @ 2310'; 100 sx @ 1660';
40 sx. @ 300'; 10 sx. @ 40' w/1 sx hulls & 1 plug. 10 sx in rathole. Total 210 sx 50-50 poz, 6%
Gel, 3% CC, 2 sx cello-flake, by Allied Cementing Co.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11-06-84

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Butch Hoberecht PHONE # (316) 265-3351
RECEIVED STATE CORPORATION COMMISSION 12-11-84 DEC 11 1984

ADDRESS 300 Sutton Place, Wichita, KS 67202 CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR Allied Cementing Co. LICENSE NO. N/A

ADDRESS P.O. Box 31, Russell, KS 67665 PHONE # (913) 483-2627

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Dan A. Bowles
(Operator or Agent)
Dan A. Bowles

CONFIDENTIAL

DATE: 12-10-84