

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15 - 039 - 20487-00-00 (of this well)  
Lease Owner D/FW Oil & Gas, Inc.  
Address Suite 603 University Tower, 6440 No. Central Expressway, Dallas, Texas  
75206  
Lease (Farm Name) SODERLUND Well No. 1  
Well Location NE SE Sec. 2 Twp. 3S Rge. 27W (E) (W) X  
County Decatur Total Depth 4080' Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin 9:00 p.m., 03-23-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 So. 2nd Street, Hill City KS

Plugging Contractor Abercrombie Drilling, Inc. License No. \_\_\_\_\_

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name D/FW Oil & Gas, Inc.

Address Suite 603 University Tower, 6440 No. Central Expressway, Dallas, Texas  
75206

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge  
Applicant or Acting Agent

Date: March 27, 1980

RECEIVED  
MAR 31 1980  
CONSERVATION DIVISION  
WICHITA, KANSAS

3-31-80

15-039-20487-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	D/FW Oil & Gas, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Soderlund #1
LOCATION:	NE SE, Section 2-3S-27W Decatur County, Kansas
SPUD DATE:	March 17, 1980
COMPLETION DATE:	March 23, 1980

0	293	Shale and sand
293	2279	Shale
2279	2311	Anhydrite
2311	3043	Shale
3043	3759	Lime and shale
3759	3970	Shale and lime
3970	4080	Lime
	4080	Rotary Total Depth

Spud hole at 8:00 p.m., March 17, 1980. Drilled 293' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 20# casing. (Tally 283.50'). Set at 291.40' with 220 sacks of Class A cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 2:30 a.m., March 18, 1980.

T.D. 4080'. Set 1st plug at 1350' with 70 sacks, 2nd plug at 280' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks and rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 9:00 p.m., March 23, 1980.

SAMPLE TOPS:

Anhydrite	2279'
B/Anhydrite	2311'

RECEIVED  
 STATE OF KANSAS  
 COMMISSIONER OF REVENUE  
 MAR 31 1980  
 CONSTITUTIONAL DIVISION  
 Topeka, Kansas  
 3-31-80


STATE OF KANSAS        )  
                                   ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Soderlund #1, NE SE, Section 2-3S-27W, Decatur County Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 27th day of March, 1980.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.

State of Kansas



15-039-20487-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
WILLIAM G. GRAY

Governor  
Chairman  
Commissioner  
Commissioner

Carol J. Larson, Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

March 28, 1980

WELL PLUGGING AUTHORITY

Soderlund Well No. 1  
C NE SE, Sec. 2-3S-27W  
Decatur County  
4080'  
Abercrombie Drilg., Inc.


D/FW Oil & Gas  
6440 N. Central Expy.  
Dallas, TX 75206

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,

  
J. LEWIS BROCK, Administrator

Mr. Gilbert Waltham, Box 9, Palco, KS 67657

is hereby assigned to supervise the plugging of the above named well