

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22759-00-00^{D1}
Spot: SENV Sec/Twnshp/Rge: 23-6S-24W
1980 feet from N Section Line, 1780 feet from W Section Line
Lease Name: WHITE Well #: 2
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W. MAIN - PO BOX 428
LOGAN, KS 67646

PROD Size: 5.5 feet: 3900 475 SX CMT
SURF Size: 8.625 feet: 246 165 SX CMT

#126 75

Well Type: EOR UIC Docket No: E27258.1 Date/Time to Plug: 07/13/2004 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JIM R BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered out 200 sxs Swift Multi-Density cement - 18 sxs gel spacer - 500# hulls.
D.V tool at 2124' with no cement amounts.
PBTD 3890'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2004 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 25 sxs SMD with 500# hulls, followed with 18 sxs gel spacer.
Topped off with 50 sxs SMD.
Max. P.S.I. 1000#. S.I.P. 800#.
Backside 500# instant pressure.

Perfs:

Top	Bot	Thru	Comments
3707	3852		

RECEIVED
JUL 15 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

7-16-04

TV. NO.

2005060062

Form CP-2/3

JUL 14 2004

HESS OIL CO
MCPHERSON KS 67460

23-06S-24W
130'E, C W/2 SE NW

#2 WHITE

off: 6 S & 1 E OF LENORA KS
contr: MALLARD JV # 1
used: JAMES C HESS

by: GRAHAM
field: HOOSIER

API 15-06S-22759

Ir date 06/28/95 spd date 07/08/95 drlg comp 07/15/95 card issued 10/16/95 last revised 03/17/97

ELV: 2437 KB, 2432 GL LOG	
tops.....	depth/datum
SC.....	.2145 + 292
B/SC.....	.2174 + 263
TOP.....	.3461 -1024
HEEB.....	.3661 -1224
LANS.....	.3703 -1266
BKC.....	.3886 -1449
PBTD.....	.3890 -1453
LTD.....	.3893 -1456
RTD.....	.3900 -1463

IP status:
OIL, P 20 BO & 18 BWP, LKC 3707-3852 OA, 07/27/95
CORR & INFO REL: 3/17/97 CORR COMP INFO.
ADDED MISC INFO
NOTE: INFO REL 11/13/95 WAS OIL WELL TIGHT HOLE
CSG: 8-5/8" 246 / 165 SX (ALT 2), 5-1/2" 3900 / 475 SX
NO CORES
DST (1) 3694-3720 (TOR, LANS), MISRUN
DST (2) 3694-3720 (TOR, LANS), / 30-30-0-0, (1ST OP)
WB, DIED/10", REC 60' M, 120' OCM (20% OIL, 80% M)
ISIP 511# IFP 123# -126# IHP 1700# FHP 1645# BHT 110

COPYRIGHT 1997
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

HESS OIL CO
MCPHERSON KS 67460

23-06S-24W
130'E, C W/2 SE NW

#2 WHITE

DST (3) 3740-3797 (LKC), / 60-60-60-60, (1ST OP) SB OFF BTM BKT/17", (2ND OP) 6 INCH BLO, REC 680' SLI MCW (CHL 26,000 PPM) ISIP 1285# FSIP 1281# IFP 143# -210# FFP 319# -323# IHP 1862# FHP 1832# BHT 122'

DST (4) 3798-3890 (LKC), MISRUN
DST (5) 3798-3890 (LKC), / 60-60-60-60, (1ST OP) WB INCR TO 1/2 INCH, (2ND OP) NB, REC 125' SLI OCM ISIP 405# FSIP 385# IFP 64# -56# FFP 113# -101# IHP 1854# FHP 1796# BHT 112

TRGT ZN: LANS, PTD 4210 (ARB), MICT - CO, PF (LKC) 3850-3852, W / 4 SPF, AC 250 GAL (15% MCA/HCL) & 500 GAL (15% HCL/NE-FE), SO, PF (LKC) 3707-3711, W / 2 SPF, AC 300 GAL (15% MCA/HCL) & 1000 GAL (15% HCL/NE-FE), SO, SET 2-7/8" TBG AT 3857, NO PKR, POP, P 20 BO & 18 BWP (GR 27), 7/27/95