

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20297-00-00
Spot: SESWNW Sec/Twnshp/Rge: 14-14S-39W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SCHMALZRIED Well #: 1
County: WALLACE Total Vertical Depth: 5150 feet

Operator License No.: 32302
Op Name: KEY GAS CORP.
Address: 155 N. MARKET - SUITE 900
WICHITA, KS 67202

PROD Size: 5.5 feet: 1250
SURF Size: 8.625 feet: 252

167³⁸

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/16/2004 10:00 AM
Plug Co. License No.: 32302 Plug Co. Name: KEY GAS CORP.
Proposal Rcvd. from: TONY NEW Company: KEY GAS CORP. Phone: (316) 265-2270

Proposed Plugging Method: Ordered 135 sxs 60/40 pozmix - 6% gel.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2004 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 252' w/160 sxs cement.
5 1/2" production casing set at 1319' w/200 sxs cement. Cement circulated to surface.
TD 5150'. PBTD 1300' with CIBP.
Cast iron bridge plug and shoe drilled out.
Ran tubing to 1751' - pumped 50 sxs cement.
Pulled tubing to 1284' - pumped 7 barrels gel spacer - pumped 25 sxs cement.
Pulled tubing to 972' - pumped 25 sxs cement - pumped 1 barrel gel spacer.
Pulled tubing to 300' - pumped 25 sxs cement - pumped 1 barrel gel spacer.
Pulled tubing to 118' - pumped 6 sxs cement - cement to surface.
Pulled tubing to surface.
Connected to 5 1/2" production casing - pumped 4 sxs cement.
Max. P.S.I. 1000#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped .50 sx cement.
Max. P.S.I. 300#. S.I.P. 0#.
Packing blew out.

Perfs:

Top	Bot	Thru	Comments
921	931		

RECEIVED
AUG 20 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #13887

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED

DATE 8-23-04
INV. NO. 2005060384

AUG 19 2004

replacement card
WILDCAT.

KEY GAS CORP
WICHITA KS 67202

14-14S-29W
SE SW NW

#1 SCHMALZRIED

site: 4-3/4 S & 1-1/4 W OF WALLACE KS	cy: WALLACE	API 15-199-20297
contr: ACE DRILL-N #1	field: WC (7 SE OF SHARON SPRINGS)	
fr date 05/13/2003	spcl date 05/27/2003	orig comp 06/17/2003
	card issued 03/01/2004	last revised 07/26/2004

ELV: 3566 KB, 3561 GL LOG	
tops	depth/datum
PBTD	1000 +2566
TOP	3953 -387
HEEB	4102 -536
LANS	4156 -590
MRW	4876 -1310
STE GEN	5003 -1437
RTD	5150 -1584

IP status:
DELAYED COMP, 02/24/2004
 INFO REL: 7/26/2004 - ADDED TOPS & MISC INFO
 NOTE: CORR 7/1/2003 - PREVIOUSLY RPTD AS D & A IN
 ERROR
 CSG: 8-5/8" 252 / 160 SX (ALT 2), 4-1/2" 1000
 NO CORES
 DSTS TAKEN - DETAILS NA
 TRGT ZN: MRW (OIL), PTD 5500 (MISS), NON-PROD DEEP,
 MICT - CO, PB 1000, PF (NIOB) 920-950, W / 4 SPF, AC 500
 GAL, SWB LD, SG ?, SI - EVAL, DELAYED COMP 2/24/2004 -
 NO OTHER INFO AVAILABLE - TEMP COMP 3/1/2004

COPYRIGHT 2004
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

RECEIVED
AUG 20 2004
KCC WICHITA