

To: **010732**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-9
API NUMBER 15-15-039-20868-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

Operator: C M X Inc.
Name & Address: 1026 V. C. Bldg.
Wichita, Ks.

C SW SW SEC. 6, T 3 S, R 20/28 W/E
660 feet from S section line
4620 feet from E section line

Lease Name Wentz Well # 1
County Decatur 123.50
Well Total Depth 3800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A xx

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling License Number _____

Address Steve Carlton

Company to plug at: Hour: _____ Day: 9 Month: Oct. Year: 19 90

Plugging proposal received from Steve Carlton

(company name) _____ (phone) _____

were: Order 190 sks cement 60/40 poz 6% gel and 2 sks f.c.

Heavy mud between all plugs.

Pump cement down drill pipe

Elevation 2637 Anhy 2200-29 Arb. No. _____

Top Dakota 1450

Plugging Proposal Received by D. F. B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:30 PM Day: 9 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 25 sks at 2225

100 sks at 1480.

40 sks at 300

10 sks at 40

15 sks in rathole

RECEIVED
STATE CORPORATION COMMISSION
10-17-90

Remarks: Allied Cementing Co.

(If additional description is necessary, use BACK of this form.)
(did/did not) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas
Signed Dale J. Balthazor
(TECHNICIAN)
Dale Balthazor

Jib-S

DATE 10-22-90

INV. NO. 29687

10-9