

6 010223

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 039-20,727 -00-00

NW, SEC. 24, T. 3 S, R. 27 W/EX
1180 feet from N/S section line
400 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Kincaid Well # 3-24

Operator: Murfin Drilling Company

County Decatur

Name & Address 250 N. Water

Well Total Depth 3635 118.14 feet

Suite 300

Conductor Pipe: Size 0 feet

Wichita, Ks. 67202

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address Same as above

Company to plug at: Hour: AM Day: 20 Month: September Year: 19 84

Plugging proposal received from Steve Carlton

(company name) Murfin Drilling Company (phone)

were: Order 185 sks cmt 50/50 pozmix 6% gel 3% cal. cl., 1 sk hulls 8 5/8" plug 1 sk flow-seal
Spot drill pipe with no less than 36 vis. mud between all plugs, with good circulation
and no fluid loss.

Elevation 2125' Anyh 2192-2224 Arbuckle No Dakota 1450

Plugging Proposal Received by Dale F. Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XX

Operations Completed: Hour: 11:30 AM Day: 20 Month: September Year: 19 84

ACTUAL PLUGGING REPORT Circulated at 2210 for 20 minutes

- 1st plug @ 2210 w/25 sks
- 2nd plug @ 975 w/100 sks mixed with 1 sk flow-seal
- 3rd plug @ 280 w/40 sks
- 4th plug @ 40 w/10 sks on solid bridge
- 10 sks in Rat Hole

Remarks: Cemented by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-2-84

INV. NO. 3978

Signed Dale F. Balthazor (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
9-24-84
SEP 24 1984

CONSERVATION DIVISION
Wichita, Kan. sec

9-21-84
MFB
30