

6 030902

15-039-30073-00-01

API NUMBER 15- 12 - 8 - 66

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NE NW, SEC. 34, T 3 S, R 27 W/E

4290 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Steffen Well # 2 SWD

Operator: Raymond Oil Co. Inc.

County Decatur 120.90

Name & Address P. O. Box 48788

Well Total Depth 3720 feet

Wichita, Kansas 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 289'

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 16 Month: June Year: 19 87

Plugging proposal received from Vernon

(company name) Kelso Casing (phone)

were: 8 5/8 set at 289' w/250 sks, 5 1/2 set at 3718 w/125 sks PBTB 3718'.

Perfs 3292' - 3660'. Order sand and Com Cmt. Shoot and pull pipe.

Order 200 sks. ATL 65/35 Poz 10% Gel 2% Dixel Allied Cmt. Co.

LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:40 PM Day: 16 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on PBTB to 3240' w/5 sks Com Cmt on sand w/bailer.

4 shots at 1600' 1400' 1200' and 1000' Recovered 1000' of 5 1/2" CSG.

Squeeze down 8 5/8 200 sks ATL Cmt blend Max. Psi. 300#.

Close in Psi. 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-21-87

INV. NO. 17539

Signed Carl Goodrow (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION JUL 16 1987 CONSERVATION DIVISION Wichita, Kansas