

15-039-30075-00-00

To: 6 030903  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION W/2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1-12-67  
NW NW, SEC. 34, T 3 S, R 27 W/2

4620 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Steffen Well # 3

Operator: Raymond Oil Co. Inc.

County Decatur 121.42

Name & Address P.O. Box 48788

Well Total Depth 3736 feet

Wichita, Kansas 67201

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 16 Month: 6 Year: 19 87

Plugging proposal received from Vernon

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 8 5/8 set at 274 ' with 250 sx 5 1/2 set at 3731 with 150 sx. Perf's 3507 - 3635'  
order sand and com. cmt. shoot and pull pipe order 200 sx ATL 65/35 poz 10% gel  
2% Dixel 6 sx hulls Allied Cmt. Co.  
LaRue Water Trucks

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:50 PM Day: 16 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on bottom to 3450' with 5 sx. com. cmt. on sand  
w/Bailer. 8 shots at 2500' 2300' 2100' 1900' 1700' 1500' 1300' and 1200'  
Recovered 1200 ' of 5 1/2" csg.

Squeeze down 8 5/8" casing 200 sx. ATL cmt. blend with 6 sx hulls mixed in  
Max. PSI 400 # close in PSI 150# plug complete.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED To serve this plugging.

DATE 7-21-87

INV. NO. 17540

Signed *Carl Goodrow*  
(TECHNICIAN)

Carl Goodrow

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 16 1987  
CONSERVATION DIVISION  
Wichita, Kansas  
7-16-87