

15-039-30071-00-00

6 030591

API NUMBER 15-

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE 1/4 SEC. 34, T. 3 S, R. 27 W

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name STEFFEN Well # 1

Operator: RAYMOND OIL CO. INC.

County DECATUR 131.30

Name & Address ONE MAIN PLACE #900

Well Total Depth 4040 feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67202

Surface Casing: Size 7" feet 290

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 4 Month: 11 Year: 19 85

Plugging proposal received from MILLARD KELSO

(company name) KELSO CASING. (phone) \_\_\_\_\_

were: 7" SET @ 290 w/150 SX. 4 1/2 SET @ 3804 w/125 SX. PBTD 3805

ORDER SAND & COM. CMT. PULL PIPE ORDER 1 BOX. 60/40 PZ 6 GEL 3 1/2

40 SX. GEL 4 SX. HULLS BJ TITAN CMT CO. LARUE WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6: PM Day: 4 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT Dump SAND TO 3480 w/4 SX. COM CMT. w/BAILER

RECOVERED 1100' OF CASING. 3 SHOTS Pump DOWN 7" 3 SX. HULLS

20 SX. GEL 100 SX. CMT MIX. + 1 SX. HULLS 20 SX. GEL. 80 SX. CMT. MIX.

MAX. PSI 300<sup>#</sup> CLOSE IN 150<sup>#</sup> PLUG COMPLETE.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED NOV 25 1985

DATE INV. NO. 11168

NOV 20 1985 CONSERVATION DIVISION Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN) 11-16-85