

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01617-00-0001 *KCC RJP 8-23-04*  
Spot: S2NENW Sec/Twnshp/Rge: 10-9S-19W  
990 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: ROSTICAL C Well #: 3  
County: ROOKS Total Vertical Depth: 3445 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: PO BOX 2757 202 SOUTH ST. FRANCIS  
WICHITA, KS 67201

PROD Size: 5.5 feet: 3443 w/150 sxs cmt  
SURF Size: 8.625 feet: 329 w/175 sxs cmt *8/11/96*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/16/2004 1:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 340-2773

Proposed Plugging Method: Perforations: 3196' - 3396'. Squeezed off (2-81). Collapsed 5 1/2" casing at 2733'.  
Arb. 3443'-3445'. OH squeezed with 65 sxs.  
PBSD 2928'. Unable to get below 1285'.  
Squeezed Dakota 3-55 at 1080' w/165 sxs; 06-74 at 580' w/100 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/16/2004 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 1275'.  
Swift Services pumped 145 sxs Swift Multi-Density cement with 500# hulls - cement circulated.  
Tubing stuck - backed off 19 joints. Left 22 joints in hole.  
Swift Services pumped 58 sxs down 5 1/2" casing.  
Max. P.S.I. 450#. S.I.P. 100#.  
Hooked up to 8 5/8" and pumped 22 sxs cement.  
Max. P.S.I. 200#. S.I.P. 75#.  
04-28-2004 - Topped off with 15 sxs Multi-Density Cement - hole full.

RECEIVED  
MAY 03 2004  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed *Richard Williams*

(TECHNICIAN)

APR 29 2004

INVOICED  
DATE 5-5-04  
INV. NO. 2004061494

SONIO PETROLEUM COMPANY

#3

ROSTICAL 'C'

10-9-1961  
S2 NE NW

Cont:

ROOKS County

E-2041 RR Comm

Comp 11/13/62

IP 52 BOPD • 308 WTR

GR 31.50/LANS 3196-3396

UCD Tags	Depth	Datum
ARMY	1448	-593
NEEB	3159	-1118
LANS	3197	-1156
ARB	3442	-1401

Casing  
 OF 329  
 5" 3443:  
 WAS: SAME OPR, ARB PROD 9/1/50:  
 NEW INFO: PB: PERF  
 RB: PERF 3196-3200; 3217-21; 3237-43; 3260-64; 3256-59; 3331-34; 3337-40; 3351-54; 3393-96; 3368-72:

MONITORING


INDEPENDENT OIL & GAS SERVICE