

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20253-00-01

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1974
11-27-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Aspen Drilling Company,
 Complete Address P. O. Box #783, Great Bend, Kansas.
 Lease Name Shirley Well No. 1
 Location CSW-NE Sec. 11 Twp. 3 Rge. (E) (W) 27
 County Decatur Total Depth 3865'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Kelso Casing Pulling,
 Address P. O. Box #176, Chase, Kansas. License No. 683
 Operation Completed: Hour 1:30 PM Day 21 Month 11 Year 1974

The above well was plugged as follows:

269'--8 5/8" Surface casing, cement circulated.
3854'--4 1/2" Production casing cemented on bottom with 175 Sx. Top of perforations @ 3738'.
Pushed plug to 3650', sanded back to 3625' and set 4 Sx. cement with dump bailer.
Pulled 4 1/2" casing and squeezed well initially with 3 sacks hulls and 10 sacks gel following with 110 Cu. Ft. cement from 1450' to 1125', then 21 sacks gel from 1125' to 285' and followed with 30 Cu. Ft. cement from 285' to 210' then 4 sacks gel from 210' to 50' and finally 15 Cu. Ft. cement from 50' to bottom of cellar. Maximum pump-in pressure-150#. FSIP-50#. (Mudding & cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/2/74
INV. NO. 370-W