

KANSAS

40
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20253-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1973
1-2-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Buttes Gas and Oil Company,
Complete Address 1776 Lincoln, Denver, Colorado. 80203
Lease Name M. H. Shirley Well No. 1
Location CSW-NE Sec. 11 Twp. 3 Rge. (E) (W) 27
County Decatur Total Depth 3865'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Murfin Drilling Company,
Address 617 Union Center, Wichita, Kansas. License No. _____
Operation Completed: Hour 6:45 AM Day 28 Month 12 Year 1972

The above well was plugged as follows:

273'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1475' and displaced 110 Cu. Ft. cement
thru DP from 1475' to 1150'. Pulled DP to 290' and displaced 30 Cu. Ft. cement thru
DP from 290' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Doherty*
Well Plugging Supervisor

INVOICED

DATE 1/3/73
INV. NO. 6801-4