

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20236-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
3-6-74

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Gillespie Well No. 2

Location CSE-SE Sec. 10 Twp. 3 Rge. (E) (W) 27

County Decatur Total Depth 3840'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:45 AM Day 28 Month 2 Year 1974

The above well was plugged as follows:

266'--8 5/8" Surface casing, cement circulated with 200 Sx.

3639'--5 1/2" Production casing cemented on bottom with 150 Sx. Top of cement @ 3216'.  
Well plugged back to 3660'. Top perforations from 3634' to 3636'.

Sanded well back to 3600' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing

(3115') and squeezed well initially with 5 sacks hulls and 9 sacks gel and followed

with 110 Cu. Ft. cement from 1150' to 1125' then 21 sacks gel from 1125' to 285' and

followed with 30 Cu. Ft. cement from 285' to 210' then 5 sacks gel from 210' to 25'

and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure

-150#. Final shut-in pressure-50#, (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 3/6/74

INV. NO. 8708-W