

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20103-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1974
CONSERVATION DIVISION
Wichita, Kansas
2-27-74

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Gillespie Well No. 1

Location CSW-SE Sec. 10 Twp. 3 Rge. (E) (W) 27

County Decatur Total Depth 3865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:15 PM Day 21 Month 2 Year 1974

The above well was plugged as follows:

232'--8 5/8" Surface casing, cement circulated with 150 Sx.
3864'--5 1/2" Production casing cemented on bottom with 175 Sx. Top of cement @ 2964'.
Top perforations from 3612' to 3614'.

Sanded well back to 3600' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(2835') and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed
with 110 Cu. Ft. cement from 1425' to 1100' then 21 sacks gel from 1100' to 260' and
followed with 30 Cu. Ft. cement from 260' to 190' then 4 sacks gel from 190' to 30'
and finally 10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure
-100#. Final shut-in pressure-50#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/27/74

INV. NO. ~~865~~ 8651-W

Signed: W. L. D'ichals
Well Plugging Supervisor