

KANSAS

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20090-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1969
CONSERVATION DIVISION
Wichita, Kansas
8-16-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dreiling & Hiko Bell Mining and Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name Brown Well No. 1

Location NE-SW-NE Sec. 28 Twp. 3 Rge. (E) (W) 27

County Decatur Total Depth 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: R. R. #2, Victoria, Kansas. License No. _____

Operation Completed: Hour 10:30 PM Day 11 Month 5 Year 1969

The Above well was plugged as follows:

182'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 1075'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 5/16/69
INV. NO. 9774-11