

KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION AGENT'S REPORT

15-039-00186-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 31 1962
 7-31-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Operator's Full Name O. A. Sutton
 Complete Address: 407 Insurance Bldg Wichita, Kansas
 Lease Name Gilbert Well No. 1
 Location SW SE NW Sec. 28 Twp. 3 Rge. (E) (W) 27
 County Decatur Total Depth 3785
 Abandoned Oil Well Gas Well Input Well SWD Well D & A x
 Other well as hereafter indicated:
 Plugging Contractor: Murfin Drg Co
 Address: Wichita, Kansas License No.
 Operation Completed: Hour 2PM Day 28 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 229' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 550', displaced 20 sax
cement through drill pipe, heavy mud to 180', set plug and 20 sax cement,
heavy mud to 35', set plug, hulls and filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
 DATE 8/1/62
 INV. NO. 5469-W

Signed: [Signature]
 Well Plugging Supervisor