

4 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-30072-00-00

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1968
CONSERVATION DIVISION
Wichita, Kansas
2-13-68

Operator's Full Name Raymond Oil Company, Incorporated.

Complete Address: 410 Fourth National Bank Building, Wichita, Kansas.

Lease Name Johnson Well No. 1

Location S/2-SW-SW Sec. 27 Twp. 3 Rge. (E) (W) 27

County Decatur Total Depth 3748'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 12:00 M Day 9 Month 2 Year 1968

The Above well was plugged as follows:

268'--8 5/8" Surface pipe, cement circulated with 250 Sx.

3748'--5 1/2" Production casing cemented with 125 Sx. Top perforations @ 3685'.

Sanded well back to 3625' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing

and squeezed well using initially 12 sacks gel and followed with 100 Sx. cement from

1150 to 825 then 13 sacks gel from 825 to 280' and followed with 20 Sx. cement then

5 sacks gel from 220' to 40' and finally 10 Sx. cement from 40' to bottom of cellar.

Maximum pump-in pressure 200#. Final shut-in pressure 50#. Mudding and cementing

operations performed by Halliburton.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Pichela*
Well Plugging Supervisor

DATE 2/13/68

INV. NO. 7263-W