

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20291-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1974
CONSERVATION DIVISION
Wichita, Kansas
12-2-74

Operator's Full Name Raymond Oil Company, Incorporated,

Complete Address 200 West Douglas, Wichita, Kansas.

Lease Name Machart Well No. 1

Location NW-NE-SW Sec. 34 Twp. 3 Rge. (E) (W) 27

County Decatur Total Depth 3600
4600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling Company, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 4:15 PM Day 25 Month 11 Year 1974

The above well was plugged as follows:

211'---8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 2250' to 925'. Pulled DP to 240' and displaced 30 Cu. Ft. cement thru
DP from 240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichole
Well Plugging Supervisor

INVOICED

DATE 12/4/74
INV. NO. 410-w