

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

20039
15-039-~~902~~-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1968
CONSERVATION DIVISION
Wichita, Kansas
4-15-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza, Wichita, Kansas.

Lease Name Machart Well No. 1

Location NE-SW-SW Sec. 34 Twp. 2 Rge. 3 (E) 43 (W) 27

County Decatur Total Depth 3705'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Paine Drilling Company, Incorporated,

Address Box "D", Hill City, Kansas. License No. _____

Operation Completed: Hour 2:30 PM Day 11 Month 4 Year 1968

The above well was plugged as follows:

290'--7" OD Surface pipe, cement circulated with 150 Sx. (6 1/4" Hole).
Top of Dakota Section @ 1065'.

Circulated hole with heavy mud. Pulled DP to 1290' and displaced 65 Sx. cement thru
DP from 1290' to 970'. Pulled DP to 300' and displaced 15 Sx. cement thru DP from
300' to 240'. Pulled DP, set bridge @ 30' with 1/2s ack hulls and 5 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Fehel
Well Plugging Supervisor

INVOICED
DATE 4/15/68
INV. NO. 7582-W