

KANSAS

Form CP-3  
Rev. 6-9-67

*SP*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20002-00-00

OCT 12 1967  
10-12-67  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Bartos Well No. 1

Location CE/2-NE-NE Sec. 33 Twp. 3 Rge. (E) (W) 27

County Decatur Total Depth 3710

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box # 364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 4:45PM Day 7 Month 10 Year 1967

The above well was plugged as follows:

231'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
3710'--5 1/2" Production casing cemented with 150 Sx. Top perforations from 3565' to 3568'.  
Dakota Section from 865' to 1025'.

Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
and squeezed well with 22 sacks gel with 5 sacks hulls in initial gel and followed  
with 100 Sx. cement from 1050' to 730' then 10 sacks gel from 730' to 240' and follow-  
ed with 20 Sx. cement from 240' to 180' then 3 sacks gel from 180' to 30' and 10 Sx.  
cement from 30' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols  
Well Plugging Supervisor

DATE 10/12/67  
INV. NO. 6483-W