



15-039-20291-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1974

CONSERVATION DIVISION
Wichita, Kansas

12-2-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Paul Flax of Abercrombie Drlg., Co., Inc., has this date requested permission to plug the following described well:

Mr. Flax guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Incorporated,

Complete Address: 200 West Douglas, Wichita, Kansas.

Lease Name: Machart Well No. 1

Location: NW-NE-SW Sec. 35 Twp. 3 Rge. (E)(W) 27

County: Decatur Total Depth 3600' 4600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flax was instructed to plug the well as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft. cement thru DP. Pull DP to 240' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichole
Conservation Division Agent