

State of Kansas



20039
15-039-~~1000~~-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1968
CONSERVATION DIVISION
Wichita, Kansas
4-15-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Duane Born of Paine Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name: Machart Well No. Kcc 1

Location: NE-SW-SW Sec. 34 Twp. 3 Rge 27 (E) (W) 27

County: Decatur Total Depth 3705' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

290'--7" OD Surface pipe, cement circulated with 150 Sx. (6 1/2" Hole).
Dakota section top @ 1065'.

Circulate hole with heavy mud. Pull DP to 290' and displace 65 Sx.
cement thru DP. Pull DP to 300' and displace 15 Sx. cement thru DP.
Pull DP, set bridge @ 40' and 8 Sx. cement to bottom of cellar.

Very truly yours,

H. B. Dehale
Conservation Division Agent