

State of Kansas



15-039-20002-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1967
10-12-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Bartos Well No. 1

Location: CE/2-NE-NE Sec. 33 Twp. 3 Rge. (E)(W) 27

County Decatur Total Depth 3710 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

231'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3710'--5 1/2" Production casing cemented with 150 Sx. Top of cement @
2670' (Temp Survey). Top perforations from 3565 - 3568'. Dakota section
from 865' to 1025'.

Sand well back to 3550' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
and squeeze well with 35 sacks gel, 5 sacks hulls and 130 Sx. cement
"staged".

Very truly yours,

N. L. Nichols

Conservation Division Agent