



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1968
CONSERVATION DIVISION
Wichita, Kansas
2-13-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Incorporated.

Complete Address: 410 4th National Bank Building, Wichita, Kansas.

Lease Name: Johnson Well No. 1

Location: S/2-SW-SW Sec. 27 Twp. 3 Rge. (E)(W) 27

County: Decatur Total Depth 3748' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

268'--8 5/8" Surface pipe, cement circulated with 250 Sx.
3748'--5 1/2" Production casing cemented with 125 Sx. Top perforations @ 3685'.

Sand well back to 3625' and set 5 Sx. cement with dumbo bailer.
Pull 5 1/2" casing and squeeze well with 30 sacks gel and 130 Sx. cement.

Very truly yours,

W. B. Nichols
Conservation Division Agent