

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
*Please TYPE Form and File ONE Copy*

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15-015-19502-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_.

Well Operator: VESS OIL CORPORATION KCC License #: 5030 6/04

Address: 8100 E. 22nd Street North, Bldg. 300 City: Wichita  
(Owner / Company Name) (Operator's)

State: KS Zip Code: 67226 Contact Phone: (316) 682 - 1537 X103

Lease: Hamilton A Well #: 18 Sec. 11 Twp. 26S S. R. 04E  East  West

App. - NE - SE - SE Spot Location / QQQQ County: Butler

1120' Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

200' Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: 10 Set at: 400 Cemented with: mudded in Sacks \_\_\_\_\_

Surface Casing Size: 8-1/4 Set at: 2043 Cemented with: mudded in Sacks \_\_\_\_\_

Production Casing Size: 6-1/4 Set at: 2359' Cemented with: mudded in Sacks \_\_\_\_\_

List (ALL) Perforations and Bridgeplug Sets: Arb OH 2359-2366, junk metal in hole @ 2302'

**RECEIVED**

Elevation: 1388 ( G.L. /  K.B.) T.D.: 2370' P.B.T.D.: 2366' Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

**MAY 13 2004**

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

**KCC WICHITA**

Proposed Method of Plugging (attach a separate page if additional space is needed): Doug Louis-District 2- Run tubing to 2300'. Spot 35 sx Class A 3% cc, plug.. Pull out. Wireline tag it, welder orange peeled 8-1/4 to 6-1/4, weld 5-1/2 collar on top. Perfs at 250'. Tie onto 6-1/4" Circ. 65/35 pozmix, 4% gel cement. Refill 6-1/4 if needed.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? no logs were run on old well - open hole Arbuckle

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: Casey Coats

Phone: (316) 682 - 1537 X104

Address: 8100 E. 22nd St., North, Bldg. 300 City / State: Wichita, KS 67226

Plugging Contractor: United Cementing and Acid, Inc. KCC License #: 30437

Address: 2510 W. 6th, El Dorado, KS 67042 Phone: (316) 321 - 4680  
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): 5/11/04 8:00 a.m. 5-12-04 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/11/04 Authorized Operator / Agent: [Signature]  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202