

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

RECEIVED
APR 19 2004
KCC WICHITA

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

15-163-01617-00-01

API # 15-163-09537-0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 8-4-50

Well Operator: Gore Oil Company KCC License #: 5552 le/04

Address: P.O. Box 2757 City: Wichita (Operator's)

State: KS Zip Code: 67201-2757 Contact Phone: (316) 263-3535

Lease: Rostocil C Well #: 3 Sec. 10 Twp. 9 S. R. 19 East West

S/2 - NE - NW Spot Location / QQQQ County: Rooks

4290 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line) RSPKC

3300 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line) 8-23-04

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 329' Cemented with: 175 Sacks

Production Casing Size: 5 1/2" Set at: 3443' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3196-3200', 3217-21', 3237-43', 3260-64', 3256-59', 3331-34', 3337-40', 3351-54', 3393-96', 3368-72'

2036/ Elevation: 2041' (G.L. / K.B.) T.D.: 3445' PBTD: _____ Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As per KCC agent's instructions.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Gary Reh

Gore Oil Company Phone: (308) 345-1597

Address: 202 Karrer City / State: McCook, NE 69001

Plugging Contractor: Swift Services, Inc. KCC License #: 32382 10/04

Address: P.O. Box 466, Ness City, KS 67560-0466 Phone: (785) 798-2300 (Contractor's)

Proposed Date and Hour of Plugging (if known?): April 16, 2004 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4-16-04 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

WELL LOG.
Sohio Petroleum Company

Lease: Rostocil "C" No. 3.
Elevation: 2039 Derrick Floor.

C-S¹/₂ NE-NW, Sec.10,
T-9, R-19W,
Rooks County, Ks.

Note: All measurements from rotary
bushings.

COMMENCED: 7-23-50
COMPLETED: 8- 4-50

0	5 Cellar
5	150 Post rock & clay
150	200 Blue shale
200	330 Blue shale & Lime shells
330	570 Shale & shells
570	620 Shale & shells
620	660 Sand
660	820 Shale & shells
820	824 Iron Pyrite
824	925 Shale & shells
925	1170 Sand
1170	1448 Shale & shells
1448	1470 Anhydrite
1470	1630 Shale & shells
1630	1730 Shale & shells
1730	1800 Shale & shells
1800	2030 Lime & shale
2030	2150 Lime shale
2150	2180 Lime
2180	2200 Lime shale
2200	2290 Lime & shale
2290	2465 Lime & shale
2465	2565 Lime & shale
2565	2600 Lime & shale
2600	2665 Lime & shale
2665	2735 Lime & shale
2735	2805 Lime & shale
2805	2890 Lime & shale
2890	2955 Lime & shale
2955	3000 Lime & shale
3000	3055 Lime & shale
3055	3100 Lime & shale
3100	3140 Lime
3140	3172 Lime
3172	3215 Lime
3215	3225 Lime
3225	3265 Lime
3265	3300 Lime
3300	3330 Lime
3330	3375 Lime
3375	3425 Lime
3425	3444 Lime
3445.48	Total Depth: (Rotary bushing Meas.)

CASING RECORD:

8 5/8" Surface casing, set at
330' w/175 sacks cement by
Halliburton.

5-1/2" production casing set at
3444 1/2' w/150 sacks cement
by Halliburton.

D.S.T. by Johnson Testing Co.

3200' to 3225' tool open 30
min. Recovered Good steady
blow, 300' Heavily oil cut
mud. B.H.P. 10 min. 1150#.
Flowing pressure -0.

Run Schlumberger and Micro
Log at total depth.

TOPS

Anhydrite	1448-1470	Lansing	3195
Topoka	2953	Arbuckle	3441
Heebner	3155-3158		

I hereby affirm that the above and foregoing is a true and correct copy of
the log of the Rostocil "C" No.3, located C-S¹/₂ NE-NW, Sec.10, T-9, R-19W,
Rooks County, Kansas.

Strain Drilling Company.

By T.C. Strain
T.C. Strain.

RECEIVED

APR 19 2004

WICHITA