

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

RECEIVED  
23 FEB 23 04  
AUG 24 2004  
Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Rice Production Company  
Address: 1219 Random Road  
Phone: (620) 793-2645 Operator License #: 31154  
Type of Well: D&A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 7/7/2004 (Date)  
by: Hays - Herb Deines <sup>KCC</sup> (KCC District Agent's Name)  
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☒ Yes ☐ No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 167-23260-0000  
Lease Name: Kaufman A  
Well Number: 6  
Spot Location (QQQQ): C - N/2 - SE - NW  
3550 Feet from ☐ North / ☒ South Section Line  
3240 Feet from ☒ East / ☐ West Section Line  
Sec. 27 Twp. 15 S. R. 12 ☐ East ☒ West  
County: Russell  
Date Well Completed: 7/7/2004  
Plugging Commenced: 7/7/2004  
Plugging Completed: 7/7/2004

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Surface Conductor & Production) |             |              |             |             |
|---------------------------|---------|------------------------------------------------|-------------|--------------|-------------|-------------|
| Formation                 | Content | From                                           | To          | Size         | Put In      | Pulled Out  |
|                           |         | <u>25'</u>                                     |             |              |             |             |
|                           |         | <u>0</u>                                       | <u>408'</u> | <u>8 5/8</u> | <u>408'</u> | <u>NONE</u> |
|                           |         |                                                |             |              |             |             |
|                           |         |                                                |             |              |             |             |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged with 145 sacks 60/40 Poz., 6% Gel., 1/4# flocele per sack. 1st. plug - 25 sacks @ 10' above arbuckle, 2nd. plug - 25 sacks @ 773', 3rd. plug - 50 sacks @ 450', wiper plug - 10 sacks @ 40' to surface. Rat hole - 15 sacks, mouse hole - 10 sacks.

Name of Plugging Contractor: Allied Cementing Company, Inc. License #: 99996  
Address: P.O. Box 31, Russell, Kansas 67665  
Name of Party Responsible for Plugging Fees: Rice Production Co.  
State of KANSAS County, Barton, ss.

\_\_\_\_\_  
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) 1219 Random Rd Hays, Kansas, KS

SUBSCRIBED and SWORN TO before me this 18 day of August, 2004  
LaVeneia Smith My Commission Expires: July 14, 2005  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas

67202 LaVeneia Smith  
Notary Public - State of Kansas  
My Appt. Expires 7-14-2005

BW