

15-039-20216-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
12-15-80
RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1982
18-23-82
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Decatur SEC. 34 TWP. 3S RGE. 27W E/W
Location as in quarters or footage from lines:
NW SW SE

Lease Owner Raymond Oil Company, Inc.
Lease Name Steffan 1-A Well No. _____
Office Address One Main Place Suite 900 Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5-24-82
Plugging completed 6-8-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

_____ Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
Producing formation _____ Depth to top _____ bottom _____ T.D. 3710'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	320'	none
				5-1/2"	3196'	995'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3450' and ran 5 sacks cement. Shot casing @2430', 2019', 1810', 1604', 1404', 1202' and 1004'. Pulled a total of 32 joints of 5-1/2" casing. Plugged well with 2 sacks hulls, 20 sacks gel, 70 sacks cement, 20 sacks gel, 60 sacks cement, released plug and displaced with 10 sacks cement, 50/50 pos, 4% gel, 3% ec.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 21st. day of June, 19 82

My Commission expires: 

[Signature]
Notary Public.