

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 DERBY BLDG,
WICHITA, KANSAS 67202

Rev. 12-11-80
FORM CP-1

WELL PLUGGING APPLICATION FORM
FILE ONE COPY

API NUMBER 15-039-20;607-00-00 (OF THIS WELL)
(THIS MUST BE LISTED, IF NO API# AVAILABLE PLEASE NOTE DRILLING COMPLETION DATE,)
LEASE OWNER K & E Petroleum, Inc.
ADDRESS 300 Hardage Center, 100 S. Main, Wichita, KS 67202
LEASE (FARM NAME) ANDERSON 'B' WELL NO. 1
WELL LOCATION 100' E of S/2 SE SW SEC. 34 TWP. 3S RGE. 27W (EAST) (WEST)
COUNTY Decatur TOTAL DEPTH 3728' FIELD NAME _____
OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A XX
WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? YES
(IF NOT STATE REASON WHY)
DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10:45 a.m., 10/08/81

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Bill Craig (Toolpusher) ADDRESS P.O. Box 297, Hill City, KS 67642
PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. _____
ADDRESS 801 Union Center, Wichita, KS 67202
INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:
NAME K & E Petroleum, Inc.
ADDRESS 300 Hardage Center, 100 S. Main, Wichita, Kansas 67202

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OF ACTING AGENT.

RECEIVED
STATE CORPORATION COMMISSION
10-20-81

CONSERVATION DIVISION
Wichita, Kansas

SIGNED: Jack Partridge
APPLICANT OR ACTING AGENT
Jack Partridge, Vice President
DATE: October 15, 1981

State

15-039-20607-00-00

CONTRACTORS WELL LOG

OPERATOR: K & E Petroleum, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: ANDERSON 'B' #1
 LOCATION: 100' E. of S/2 SE SW, Sec. 34-3S-27W, Decatur County, Kansas
 SPUD DATE: 10/03/81
 COMPLETION DATE: 10/08/81

0	367	Top Soil, Sand, & Shale
367	791	Sand & Shale
791	1600	Shale & Sand
1600	2099	Sand & Shale
2099	2132	Anhydrite
2132	3050	Shale
3050	3458	Lime & Shale
3458	3728	Lime
	3728	Rotary Total Depth

Spud hole @ 12:15 a.m., 10/03/81. Drilled 367' of a 12 1/2" hole. Ran 9 jts. of 8 5/8" 20# casing set @ 366' and cemented with 175 sx. Class A Cement, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 6:00 p.m., 10/03/81.

3728' TD. Set 1st plug @ 1209' with 70 sx. Set 2nd plug @ 380' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 6% gel. Plug was down @ 10:45 a.m., 10/08/81.

SAMPLE TOPS:

Anhydrite 2099'
 B/Anhydrite 2132'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the ANDERSON 'B' #1, 100' E of S/2 SE SW, Sec. 34-3S-27W, Decatur County, KS.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state, as of this 15th day of October, 1981.

Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my commission expires 7-13-85



STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202-1286

INVOICE and WELL PLUGGING AUTHORITY

November 22, 1981

8378-W

INVOICE NUMBER:

15-039-20607-00-00

TO: K & E Petroleum, Inc.
100 S. Main
Ste. #300
Wichita, KS. 67202

PLUGGING ASSESSMENT AS FOLLOWS:

PAYABLE UPON RECEIPT

Anderson "B" #1
100' E S $\frac{1}{2}$ SE SW, Sec. 32-3S-27W
Decatur
T.D. 3728-W

\$121.16

NOTE: We also need the following before our file is completed:

- _____ Well Plugging Record (CP-4)
- _____ Well Log
- _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



Administrator

Mr. Carl Goodrow, Box 189, Penokee, KS., 67659

is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE