

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
Wichita, Kansas 67217

Rev. 3-15-72  
FORM CP-1

12-3-74  
RECEIVED  
STATE CORPORATION COMMISSION  
1974  
RECEIVED  
STATE CORPORATION COMMISSION  
11-13-74  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
File One Copy

15-039-20291-00-00

Lease Owner Raymond Oil Company  
Address 200 W. Douglas, Suite 800, Wichita, Kansas 67202  
Lease (Farm Name) MACHART Well No. #1  
Well Location C NW NE SW Sec. 34 Twp. 3 Rge. XX 27 (W)  
County Decatur Total Depth 3600' Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log filed with application as required Yes  
Date and hour plugging is desired to begin 4:15 p.m., November 25, 1974

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Joe Weber Address Ellis, Kansas

Plugging Contractor Abercrombie Drilling, Inc. License No. 746

Address 801 Union Center, Wichita Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Raymond Oil Company

Address 200 W. Douglas, Suite 800, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack K. Wharton  
Applicant or Acting Agent  
Jack K. Wharton  
Date: November 26, 1974

15-039-20291-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Raymond Oil Company, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	MACHART #1
LOCATION:	C NW NE SW Sec. 34-3S-27W Decatur County, Kansas
GEOLOGIST:	Bill Iverson
SPUD DATE:	November 20, 1974
COMPLETION DATE:	November 25, 1974

0	219	Clay, Shale & Sand
219	1775	Shale
1775	1878	Sand
1878	2086	Shale
2086	2119	Anhydrite
2119	2898	Shale
2898	3600	Lime & Shale
	3600	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
11-03 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Drilled 219' of 12 1/4" surface hole. Set 10 jts. 8 5/8" casing @ 211.17' G.L. Cemented with 150 Sacks Common, 3% Ca.Cl. Cement circulated. Plug was down @ 1:00 a.m., November 20, 1974.

D & A: 1st Plug set @1250' with 110 cu. ft. Cement; 2nd Plug set @240' with 30 cu. ft. Cement; 3rd Plug set @40' with 10 cu. ft. Cement; Plug was down @ 4:15 p.m. November 25, 1974.

<u>SAMPLE TOPS:</u>			<u>ELEVATION:</u>
Anhydrite	2086	(+475)	2561 K.B.
B/Anhydrite	2119	(+442)	2559 D.F.
			2553 G.L.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 5 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
12-5-74

STATE OF KANSAS            )  
  )   SS  
COUNTY OF SEDGWICK    )

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the MACHART #1, C NW NE SW Section 34-3S-27W, Decatur Co., Kans.


ABERCROMBIE DRILLING, INC.

By: *Jerry A. Langrehr*  
Jerry A. Langrehr  
Executive Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 2nd day of December, 1974.

*Nancy E. Bledsoe*  
Nancy E. Bledsoe- Notary Public

My Commission Expires:  
April 8, 1978



State of Kansas



15-039-20291-00-00

*State Corporation Commission*

**CONSERVATION DIVISION**

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

December 3, 1974

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Machart
Description	NW NE SW 34-3-27W
County	Decatur
Total Depth	3600'
Plugging Contractor	Abercrombie Drilling


Raymond Oil Company, Inc.  
200 West Douglas  
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. W. L. Nichols, P. O. Box 157, Morland, Kansas 67650  
is hereby assigned to supervise the plugging of the above  
named well.