

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

15-039-00043-00-00

Lease Owner Harry Gore Address 100 Brown Bldg. Wichita, Ks.
(Applicant)

Lease (Farm Name) Frickey Well No. 1

Well Location NW NW SW Sec. 31 Twp. 3 Rge. (E)-(W) 27

County Decatur Field Name (if any) _____

Total Depth 4355' Oil _____ Gas _____ Dry Hole x

Was well log filed with application? _____. If not, explain: _____

Log will be filed with application.

Date and hour plugging is desired to begin 10 a.m. 8-6-51

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.

(Use an additional sheet if necessary) _____

Name of the person on the lease in charge of well for owner _____

L. E. Bernd Address P.O. Box 229 McPherson, Kansas

Name of Plugging Contractor The Veeder Supply & Development Company

Address P. O. Box 201, Cherryvale, Kansas

Invoice covering assessment for plugging this well should be sent to

Harry Gore Address Wichita, Kansas

and payment will be guaranteed by applicant.

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1951

8-21-51
Floyd H. Held.
Applicant or Acting Agent

CONSERVATION DIVISION
Wichita, Kansas

Date 8-6-51

PLUGGING
FILE SEC T R

15-039-00043-00-00

Company Harry Gore

Sec. 31 T. 3 R. 27W

Farm Frickey

No. 1

Loc. NW NW SW

County Decatur - Kansas

Total Depth 4355'

Comm. 7-25-51

Comp. 8-6-51

Shot or Treated

Contractor Veeder Supply Co.


Drilled with Rig - D

Issued

No. of Days - 13

Casing

No. of Bits - 12



20 in. 10 in
 15 1/2 8 1/4
 12 1/2 6 5/8
 13 3/8 5 3/16

Set 214' of 8-5/8" Casing Cemented with 150 sacks cement.

Elevation

Production

Figures Indicate Bottom of Formation

Clay Sand	0	30	30
Sandy Lime	30	150	120
Line Shale	150	230	80
Blue Shale	230	550	320
Shale	550	900	350
Shale Sand	900	1120	220
Shale Shells Sand	1120	1230	110
Shale Sand	1230	1370	140
Shale Shells	1370	2150	780
Shale Shells Red Bed	2150	2375	225
Shale Shells	2375	2428	53
Anhydrite	2428	2455	27
Shale Shells	2455	2640	185
Shale Lime	2640	2705	65
Shale Lime Shells	2705	2915	210
Shale Shells	2915	2995	80
Line Shale	2995	3460	465
Line	3460	3815	355
Line Cherty	3815	3862	47
Lime	3862	3865	3
Lime Shale	3865	4185	320
Conglomerate	4185	4250	65
Conglomerate Cherty Shale	4250	4310	60
Lime	4310	4355	45
Total Depth	4355'		

Plugged @ 200 feet with 15 sacks cement.
 Plugged @ 40 feet with 10 sacks cement.

PLUGGING
 FILE SEC—T—R—
 BOOK PAGE—LINE—

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 21 1951 8-21-51
 CONSERVATION DIVISION
 Wichita, Kansas



15-039-00043-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

August 9, 1951

Well No. 1
Lease Fricks
Description SW SW SW E-1-27N
County Decatur
File No. 101-33

Mr. Harry Gore
400 Brown Bldg.
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. ~~Wilson Petty~~, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR